

PHILIPPINE SCIENCE HIGH SCHOOL SYSTEM		PURCHASE ORDER			
Office/ Campus:	CID/Bicol Region Campus				
Address/ Contact Details:	Tagongtong, Goa, Camarines Sur				
Supplier :	PIXEL8 WEB SOLUTION AND CONSULTANCY INC.	P.O. No. :	205-2018		
Address :	Brgy. 40, Cruzada, Legazpi City	Date :	9/17/2018		
TIN :	009-535-219-000	Mode of Procurement :	Rebidding		
Gentlemen: Please furnish this Office the following articles subject to the terms and conditions contained herein:					
Place of Delivery :	Tagongtong, Goa, Camarines Sur	Delivery Term :	60 days		
Date of Delivery :		Payment Term :	after final inspection		
Stock/ Property No.	Unit	Description	Quantity	Unit Cost	Amount
	units	Procurement of CCTV Cameras and Other ICT Equipment (Supply, Delivery, Installation and Configuration) Network Video Recorder (NVR) 32 channel Processor up to ARM Quad Core 32 Channel 16 PoE Ready Interface HDMI, VGA Compression H, 265/H.264 H.265+ Advance Compression Record Rate: 200Mbps Configurable Ethernet ports: Gigabit port Alarm I/O port Audio I/O port 4 slots SATA/Hardisk Power Supply: AC 100v-240v	4	32,250.00	129,000.00
	units	24-Port PoE Switch 24 Ports 802.3at/af-complaint PoE with SFP ports power supply can support 24 Ip cameras	5	22,842.00	114,210.00
	units	16-Port PoE Switch 16 Ports 802.3at/af-complaint PoE with SFP ports Power supply can support 16 Ip cameras	3	15,120.00	45,360.00
	units	SFP Gigabit Module Gigabit Module Compatible to existing PSHS-BRC network Multimode	12	1,710.00	20,520.00
	units	Fixed Camera UI is UL certified Bullet type or Dome type depending on location IR Range 30M HD 1080p video output Progressive scan CMOS Adaptive IR LED	128	3,438.00	440,064.00

		Network Connection RJ45 Compression			-
		H.264			-
		ONVIF Complaint			-
		Power source PoE CE, IP66, UI			-
		IP Camera			-
		Mounting bracket included			-
		Multi-streaming (should support at least 2 streams for Multistreaming)			-
		(12VDC/PoE, Micro SD)			-
		Ability to assign username and password			-
units		TV Display 40"	6	25,348.70	152,092.20
		LED TV			-
		Interface HDMI, VGA			-
		Including Bracket, remote control and support			-
sets		Desktop PC for Remote Viewing	1	103,955.70	103,955.70
		Good to monitor 64 cameras/Doesn't lag or pixelated			-
		Inter Core 17			-
		Minimum of 4Gb Video Memory-(should be separate card, not be build in)			-
		8 GB or higher RAM			-
		500 GB or higher HDD			-
		FSP HP 70K 700W 80 plus			-
		USB Mouse, keyboard			-
		With Licensed Proprietary 64 Bit Operating System			-
unit		Customized Floor Mounted Data Cabinet 7ft bare structure w/ four (4) standard square hole vertical mounting rails	1	70,560.00	70,560.00
		2-vented detachable side panels w/ lock and louvers, detachable vented rear back door w/ lock and louvers, detachable flexi-glass front door w/ lock			-
		600mmW x 800mmD x 7ftH			-
		Power strip w/ 12 pcs 3-pronged 220V convenient outlets w/ power cord			-
		12 pcs rear vertical cable management, 4-pcs exhaust fans on top frame w/ cable access hole			-
		4 pcs heavy duty caster wheels, 4-pcs levelling ft, color is black			-
		Powder coated finished w/ 28-pcs cage nuts			-
pcs		HDMI patch connection to video out 4 meters	8	380.00	3,040.00
pcs		Internal HDD-4 TB Internal HDD	16	10,234.00	163,744.00
lot		UTP cable Cat6, UL Listed, 4 pairs	1	63,360.00	63,360.00
units		Patch panel 24 ports Cat6	7	2,301.00	16,107.00
pcs		Patch cord 1meter Cat6-Color: Blue	128	278.60	35,660.80
pcs		Patch cord 1meter Cat6	140	14.00	1,960.00
units		Cable manager 2RU	6	4,430.40	26,582.40
pcs		Fiber patch cord 3meters	7	735.80	5,150.60
units		Costumized Wall Mounted Data Cabinet 2ftH bare structure w/ four (4) standard square hole vertical mounting rails	2	17,820.00	35,640.00
		2 vented detachable side panels w/ lock and louvers			-

		detachable flexi glass front door w/ lock 600mmW x 600mmD x 2ftH power strip w/ 4 pcs 3-pronged 220V convenient outlets w/ power cord 4 pcs rear vertical cable management 2 pcs exhaust fans on top frame w/ cable access hole color is black, powder coated finished w/ 16 pcs cage nuts			- - - - - - -
	units	TVSS- Transient Voltage Surge Suppressor Single phase 100KA per phase 220VAC NEMA Enclosure Type 1 Simple Visual Indicator for Monitoring TVSS Grounding	1	2,790.00	2,790.00
	lot	Electrical Works per IDF and MDF and grounding bus bar, grounding wire 5.5mm	1	30,000.00	30,000.00
	units	UPS #1- minimum of 2 ports	2	9,576.00	19,152.00
	units	UPS #2 1.5 KV/A 220 to 240 output voltage, rack mounted minimum of 2 ports	1	14,364.00	14,364.00
	lot	Roughing- Ins materials Labor cost- Installation, configuration, Commissioning, testing, focus, simulation	1	150,000.00	150,000.00
	lot	and training, Including documentation	1	400,000.00	400,000.00
	lot	Other items necessary to complete this project's objectives	1	10,000.00	10,000.00
		warranty. 20 years product warranty from the cabling manufacturer of the product offered (for fiber optics) and 3 years CAT6 Cable; 1 year warranty on workmanship; 3 years warranty on the entire hardware products The period for correction or defects in the warranty period is for a maximum period of thirty (30) days.			- - - -


(Total Amount in Words) Two Million Fifty Three Thousand Three Hundred Twelve Pesos and 70/100.Pesos
Only.

2,053,312.70

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent
for every day of delay shall be imposed on the undelivered item/s.

Conforme:

Very truly yours,


GERALD RAYMOND
 Signature over Printed Name of Supplier
09/19/18
 Date


ELSIE G. FERRER
 Director III

Date

Fund Cluster : 01 101 101

ORS/BURS No

Funds Available :

Date of the ORS/BURS:


CLINT D. PLAZO
 O.I.C. Accountant

Amount :